



UDUPI COCHIN SHIPYARD LIMITED

(Formerly TEBMA Shipyards Limited)

Ministry of Ports, Shipping and Waterways,
Government of India

CONTRACT CELL DEPARTMENT

CORRIGENDUM - 1 Dated: 19-01-2024

Tender No.: UCSL/CC/T/W/011

Sir,

CORRIGENDUM-1 ANNEXURE V

The following terms of the subject tender is amended as follows:

1. Annexure V - Price Bid Format corrected
2. All the other terms and conditions of the tender enquiry remains unchanged.

For Udupi Cochin Shipyard Limited,

Assistant General Manager (Materials & Contract Cell)

सोणि क्लेमेन्ट टी एम
SONY CLEMENT T M
सहायक महाप्रबन्धक ASSISTANT GENERAL MANAGER
उदुपि कोचीन शिपयार्ड लिमिटेड
UDUPI COCHIN SHIPYARD LIMITED
माल्पे, कर्नाटक/MALPE, KARNATAKA-576 108



Udupi Cochin Shipyard Limited
Tender For Hull Outfit Structural Works On 3800 DWT General Cargo Vessel
UCSL/CC/T/W/011 Dt 16th January 2024

PRICE BID FORMAT

TENDER FOR HULL FABRICATION & ERECTION OF 3800 DWT GENERAL CARGO VESSEL							
Sl.No	Scope of Work	UOM	Qty	References	Remarks	Rate /Qty	Total Price
1	Manhole - Fit up, welding, dry survey including box up and stud protection.(UCSL will supply the required manholes for installation)	Nos	83				
2	Vertical ladder (including tank ladder) - Fit up, welding, Dry survey, Final securing etc., (UCSL will supply the required ladder for installation)	Nos	56	Typical drawing attached (UY165-3141-Ladders and stairs Arrangement)			
3	Bottom plug - fit up, welding, dry survey including vacuum test and Boxing up the tank.(UCSL will supply the required bottom plugs for installation)	Nos	31				
4	Rungs & Handles - Fabrication & Installation (UCSL will supply the FB and Square bars for Fabrication and onboard erection)	Nos	80				
5	Anodes - Pad fit up, welding, dry survey and installation of anodes.(UCSL will supply the Anodes and required raw materials)	Nos	30				
6	Bilge keel - Fitment, welding and dry survey (Port & Stbd). (UCSL will supply the FB and bulb angles)	Shipset	1	Typical drawing attached (UY165-2051-Bilge keel arrangement)			





Udupi Cochin Shipyard Limited
Tender For Hull Outfit Structural Works On 3800 DWT General Cargo Vessel
UCSL/CC/T/W/011 Dt 16th January 2024

7	Eco sounder & doppler Speed log (~150mm dia) - Fitment, welding, dry survey including vacuum/hose test. (UCSL will supply the Eco sounder & doppler Speed log for installation)	Nos	2				
8	Sea Chest gratings - Fabrication & Installation (UCSL will supply the required materials for sea chest fabrication & erection)	Shipset	1	Typical drawing attached (UY165-3003- Sea Chest Arrangement & UY165-3182-Sea inlet openings arrangement)			
9	Bow thruster Grating (P&S) - Fabrication & Installation.(UCSL will supply the required materials for sea chest fabrication & erection)	Nos	1				
10	Hull marking (across ship), Tank boundary markings (as per tank plan), Draft marking (6 Locations), Plimsol marking (2 no's).	Set	1				
11	Vessel name, Owner logo, Builder logo IMO number, port of registry (Aft and fwd of vessel P&S)	Set	1				
12	Flush type D-Ring (Lashing Pot) - Fitment, welding and dry survey. (UCSL will supply the Flush type D-Rings (Lashing Pot) for installation)	Nos	34				
13	Structural Fender (76 x 38 mm dia Half round bar) fitment, welding and dry survey.(UCSL will supply the 76 x 38 mm dia Half round bar)	Rmtr	460	Typical drawing attached (UY165-2052-Fender arrangement)			
14	Double bollard - Fitment, welding and dry survey including DP Test. (UCSL will supply the Double bollard for installation)	Nos	16				





Udupi Cochin Shipyard Limited
Tender For Hull Outfit Structural Works On 3800 DWT General Cargo Vessel
UCSL/CC/T/W/011 Dt 16th January 2024

15	Warping roller - Fitment, welding and dry survey including DP Test. (UCSL will supply the Warping roller for installation)	Nos	2				
16	Panama Chock - Fitment, welding and dry survey including DP Test. (UCSL will supply the Panama Chock for installation)	Nos	13				
17	Three Row Hand Rail (Top pipe Ø 42 x 3.25, Bottom two rows 20 dia solid bar) fabrication & Installation. (UCSL will supply the pipes, solid bar and stanchion post for fabrication & installation)	Mtr	300				
18	Staircase ladder Fabrication & erection including removable type hand rail - Approx 3 meter height. (UCSL will supply the plates and gratings for fabrication & erection)	Nos	15	Typical drawing attached (UY165-3141-Ladders and stairs Arrangement			
19	Storm Rail Fabrication & erection. (UCSL will supply the pipes for fabrication & erection)	Mtr	70				
20	Equipment lifting eyes various capacity (approx. 3 Ton capacity) - Fitment, welding and dry survey including DP Test. (UCSL will supply the plates for fabrication & erection)	Nos	60				
21	Gutter-ways - Fitment, welding and dry survey. (UCSL will supply the FB for fitment)	Mtr	260	UY165-3004-Arrangement			
22	Drip-trays - Fabrication & Erection. (UCSL will supply the plates, angles and drain plugs for fabrication & erection)	Nos	12	UY165-3004-Arrangement			
23	Light box hatches Fabrication & Erection (Approx Size 600mm x 600mm) (UCSL will supply the plates for fabrication & erection)	Nos	6				





Udupi Cochin Shipyard Limited
Tender For Hull Outfit Structural Works On 3800 DWT General Cargo Vessel
UCSL/CC/T/W/011 Dt 16th January 2024

24	Under deck carling - Fitment, welding and dry survey. (UCSL will supply the plates for fabrication & erection)	Mtr	120				
25	Rungs & handles Fabrication & erection. Accessing ventilation hatches.(UCSL will supply the FB and Square bars for the Fabrication & Installation)	Nos	30				
26	Propulsion room raised platform fabrication, erection and securing the gratings. Platform Height : Approx 2 meter Material : ISMB Beam / ISMC Channel (UCSL will supply the ISMB/ISMC and Gratings for the Fabrication & Installation)	Sq. meter	60				
27	Bow thruster room raised platform fabrication, erection and securing the gratings. Platform Height : Approx 0.8 meter Material : MS Angle (UCSL will supply the MS angles and Gratings for the Fabrication & Installation)	Sq. meter	14				
28	Walkway platform Boat Deck - Fabrication, erection nd securing the gratings. (UCSL will supply the MS angles and Gratings for the Fabrication & Installation)	Sq. meter	4				
29	Walkway platform Void Deck - Fabrication, erection nd securing the gratings.(UCSL will supply the MS angles and Gratings for the Fabrication & Installation)	Sq. meter	12				





Udupi Cochin Shipyard Limited
Tender For Hull Outfit Structural Works On 3800 DWT General Cargo Vessel
UCSL/CC/T/W/011 Dt 16th January 2024

30	Walkway platform Wheel house Deck - Fabrication, erection and securing the gratings.(UCSL will supply the MS angles and Gratings for the Fabrication & Installation)	Sq. meter	7				
31	Walkway platform Wheel house top Deck - Fabrication, erection and securing the gratings.(UCSL will supply the MS angles and Gratings for the Fabrication & Installation)	Sq. meter	4				
32	Raised floor works in various locations (Including chequered plate cutting, positioning and securing).	Sq. meter	120				
33	Auxiliary Expansion tank installation	Nos	1				
34	Life craft positioning - Platform Fabrication & Erection (Port & Stbd)	Nos	2				
35	LSA & FFA - Items installation and survey.	Shipset	1				
36	Generator room exhaust - Access platform fabrication & erection to access the exhaust. (UCSL will supply the required MS Angles and Gratings)	Sq. meter	4				
37	Gangway platform - Fabrication & erection (UCSL will supply the required MS Angles and Gratings)	Nos	2				
38	Exhaust silencer platform inside funnel & extended platform. (UCSL will supply the required MS Angles and Gratings)	Sq. meter	50				
39	Steel rack fabrication & erection for stores/spares including wooden positioning & securing.(UCSL will supply the required materials)	Sq. meter	30				
40	CO2 Room Arrangement - Erection of CO2 cylinders including securing arrangement.	SET	1				
41	Fabrication & Erection of Aft Mast	SET	1	Typical drawing attached (UY165-			





Udupi Cochin Shipyard Limited
Tender For Hull Outfit Structural Works On 3800 DWT General Cargo Vessel
UCSL/CC/T/W/011 Dt 16th January 2024

				3125- Arrangement Aft Mast)			
42	Fabrication & Erection forward mast	SET	1	Typical drawing attached (UY165- 3126- Arrangement fore mast)			
43	Installation of Hatches. (Fit-up, welding, Dry survey and Hose test)(UCSL will supply the Hatches)	Nos	26	Typical drawing attached (UY165- 3142- Arrangement Small Hatches and Ventilation Openings)			
44	Anchor Winch foundation, chain stopper, bitter end - Fabrication & Erection	Nos	1	Typical drawing attached (UY165- 3153-Rev00-Anchor pocket arrangement, incl. hawse pipe and chain locker)			
45	Embarkation & Pilot ladder - Installation and securing. (UCSL will supply the Embarkation & Pilot ladder for installation).	Nos	4				
46	Expansion tank & foundation - Fabrication & Erection. (UCSL will supply required Plates and angles for fabrication & erection of expansion tank and foundation)	Nos	1				
47	Fabrication of racks in Paint store, forecastle store, Main store, linen store, Provision store (4 tire racks). Wooden planks to be installed as per site conditions.	Shipset	1				
48	Fabrication & installation of bilge well gratings	Nos	8				
49	Foundation for drilling machine & welding machine	Nos	2				





Udupi Cochin Shipyard Limited
Tender For Hull Outfit Structural Works On 3800 DWT General Cargo Vessel
UCSL/CC/T/W/011 Dt 16th January 2024

50	E motors and gearbox foundation - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2	Typical drawing attached (UY165-2071-Foundation for e motors and gearbox)			
51	Steering gear foundation - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2	Typical drawing attached (UY165-2073-working-Foundation steering gear)			
52	Bow thruster foundation - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1	Typical drawing attached (UY165-2075- Foundation bow thruster)			
53	Diesel generator set foundation - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	3	Typical drawing attached (UY165-2076- Foundation generator set)			
54	General service pump foundation - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 50KG		
55	Stop/Stripping pump foundation - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		
56	Bilge ejector foundations - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 50KG		
57	Foundation for Bilge pump in propulsion room - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		
58	Foundation for Oily water separator - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 100KG		
59	Foundation for ballast treatment plant - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 200KG		





Udupi Cochin Shipyard Limited
Tender For Hull Outfit Structural Works On 3800 DWT General Cargo Vessel
UCSL/CCTW/011 Dt: 16th January 2024

60	Foundation for fire pump - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		
61	Foundation for FO transfer pump - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 50KG		
62	Foundation for cooling water circulation pump - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 50KG		
63	Foundation for fuel oil purifier - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 50KG		
64	Foundation for FO transfer pump for Emergency generator - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		
65	Foundation for HT cooling water pump - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 50KG		
66	Foundation for combined plate coolers - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 50KG		
67	Foundation for electrical driven LT cooling water circulation pumps	Nos	2		Below 50KG		
68	Foundation for Potable/FW pumps	Nos	2		Below 50KG		
69	Foundation for UV stabilizer and filter - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		
70	Foundation for Insulated electrical boiler - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		
71	Foundation for circulating pump - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		
72	Foundation for STP - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 200KG		
73	Foundation for Sewage discharge pump - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		





Udupi Cochin Shipyard Limited
Tender For Hull Outfit Structural Works On 3800 DWT General Cargo Vessel
UCSL/CC/T/W/011 Dt 16th January 2024

74	Foundation for Electrically driven dirty oil pump - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		
75	Foundation for water cooled heat pump system - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		
76	Foundation for Emergency/Harbour generators - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 200KG		
77	Foundation for Reluctant feed pump - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		
78	Foundation for Mooring capstan - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 150KG		
79	Foundation for Air compressors - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 100KG		
80	Foundations for Air receivers - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		
81	Foundation for Air dryer - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 50KG		
82	Radar foundation - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 50KG		
83	Search light foundations - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 50KG		
84	Hand pump foundation (LO System) - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	4		Below 50KG		
85	Life raft foundation - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2				
86	MOB boat foundation - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1				
87	Foundation for chiller plant & AHU - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos			Equipment weight ~ 1.5T		





Udupi Cochin Shipyard Limited
Tender For Hull Outfit Structural Works On 3800 DWT General Cargo Vessel
UCSL/CC/T/W/011 Dt 16th January 2024

88	Foundation for propulsion panel - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 100KG		
89	Foundation for Break resistor - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 100KG		
90	Foundation for ESB - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Below 100KG		
91	Foundation for navigation & side light arrangements - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	2		Below 50KG		
92	Shaft guard - Fabrication & Erection (fit up/welding/dry survey, etc..)	Rmtr	2				
93	Ballast treatment plant UV Panel foundation - - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Equipment weight ~1.25T		
94	MSB foundation - Fabrication & Erection (fit up/welding/dry survey, etc..)	Nos	1		Equipment weight ~ 2.5T		
		Nos	1		Equipment weight ~ 2.3T		
		Nos	1		Equipment weight ~ 1.0 T		
		Nos	1		Equipment weight ~ 1.0T		
95	TOTAL AMOUNT						
96	IGST/GST @.....						
97	Grand Total						





Udipi Cochin Shipyard Limited
Tender For Hull Outfit Structural Works On 3800 DWT General Cargo Vessel
UCSL/CC/T/W/011 Dt 16th January 2024

Note:

- 1.1. Prices are to be quoted in the Pricing Format. The quotations to be submitted in the company letter head and forwarded to contractcell@udupicsl.com
- 1.2. Quotations shall be submitted as Password Protected File. The bidders are advised to share the password through only SMS while opening the quotations.
- 1.3. L1 will be determined based on the total amount at sl no.95

