



UDUPI COCHIN SHIPYARD LIMITED

UDUPI COCHIN SHIPYARD LIMITED

(Formerly TEBMA Shipyards Limited)

Ministry of Ports, Shipping and Waterways,
Government of India

CONTRACT CELL DEPARTMENT

CORRIGENDUM - 1

Tender No.: UCSL/CC/T/CIVIL/242

Date: 16.03.2024

Sir,

CORRIGENDUM-1- TENDER FOR ROOF REPAIR WORKS AT UCSL-MALPE

The following terms of the subject tender is amended as follows:

1. Extension of Tender Opening Date:

FOR:

Tender No. & date	UCSL/CC/T/CIVIL/242 Dt. 11 th MARCH 2024
Name of work	TENDER FOR ROOF REPAIR WORKS
Last date & time of receipt of tender	18 th March 2024 (Monday), 16:00 Hrs.
Date & time of opening of Technical Bid (Part-I)	18 th March 2024 (Monday), 16:00 Hrs.

READ AS:

Tender No. & date	UCSL/CC/T/CIVIL/242 Dt. 11 th MARCH 2024
Name of work	TENDER FOR ROOF REPAIR WORKS
Last date & time of receipt of tender	19 th March 2024 (Tuesday), 16:30 Hrs.
Date & time of opening of Technical Bid (Part-I)	19 th March 2024 (Tuesday), 16:30 Hrs.



2. Revised Scope of work.

FOR:

- 3.2.2. Purlin in each span is 4Nos. (2nos each side) and they are 3-point purlin fabricated ISA 75x75x6 and solid round bar ISRO 20 as cross bracings.
- 3.5. Applying one coats of Primers and two coats of enamel paints on the surface of purlins /rafters/steel structures as per the specifications given by the UCSL.
- 3.8. All the materials like Sheets, Self-tapping Screws, Primers, paints and all other consumables will be purchased by the contractor. The scope includes loading, unloading, shifting, stacking of such materials involved in the scope.
- 6.1. Necessary Scaffolding / Manlift as required for movement of man and materials to the roof is to be arranged by the contractor.
- 9.2 The work to be completed in all respect within 60 days from the date of placement of work order.

READ AS:

- 3.1.6. Crimping sheets to be provided for the pipe shop for approx. 61 Mtr.
- 3.2.2. Purlin in each span is 4Nos. (2nos each side) and they are 3-point purlin fabricated ISA 75x75x6 and solid round bar ISRO 20 as cross bracings. UCSL will supply ISA 75x75x6 and solid round bar ISRO 20 for the scope and loading/unloading is under contractor scope for the materials.
- 3.5. Applying one coats of Primers and two coats of enamel paints on the surface of purlins /rafters/steel structures at height will be under contractor scope and the paint application at ground level and supply of paints for entire scope will be under UCSL.
- 3.8. All the materials like Sheets, Self-tapping Screws and all other consumables will be purchased by the contractor. The scope includes loading, unloading, shifting, stacking of such materials involved in the scope.
- 6.1. Necessary Scaffolding / Manlift as required for movement of man and materials to the roof is to be arranged by the contractor, if required as per site conditions. UCSL will provide the service of crane/hydra for the scope of works, as per availability.
- 9.2 The work to be completed in all respect within 45 days from the date of placement of work order.

4. Revised price bid format is enclosed as ANNEXURE-V. Rev-01
5. Revised BOQ is enclosed as ANNEXURE-II. Rev-01
6. All the other terms and conditions of the tender enquiry remains unchanged.

For Udupi Cochin Shipyard Limited,



Assistant General Manager (Materials & Contract Cell)



सोणि क्लेमेन्ट टी एम
SONY CLEMENT T M
सहायक महाप्रबंधक / ASSISTANT GENERAL MANAGER
उडुपि कोचीन शिपयार्ड लिमिटेड
UDUPI COCHIN SHIPYARD LIMITED
माल्पे, कर्नाटक / MALPE, KARNATAKA-576 108



ANNEXURE -II

Rev-01

Udupi Cochin Shipyard Limited
Tender for Roof Repair Works at UCSL Malpe
UCSL/CC/T/CIVIL/242 Dt 11th March 2024**Indicative BOQ for proposal of NBS monitor roof and Pipe shop roof repair works at
UCSL-Malpe**

Sl no.	Work Description	No.s	Length(m)	Width (m)	Quantity	UOM	Unit weight	Total weight	
1	Pipe shop								
a	Replacement of roof sheets with buffing&painting of roof members	1	61	22	1342	Sqm			
b	Crimping sheets	1	61		61	Rmt			
2	Purlins								
a	3-point purlin (ISA 75*75*6)	16	28.92		462.72	Rmt	6.8	3146.50	
b	3 point purlin- lacing rods 20mm dia solid bar(ISRO20)	16	58.938		943.008	Rmt	2.4	2263.22	
								5409.72	KG
2	Crimping sheets	2	40	3	480	Sqm			
3	L flash sheets (500*500) 0.50mm thk	1	300		300	Rmt			

Work Description:**1. Pipe shop roof sheet replacement**

- This work includes removal of existintg corroded galvalume roof sheets entirely from the roof, buffing and painting of the purlin members which are in contact with sheets and fixing new sets of galvalume corrugated sheets. One coat of primer and two coats of enamel paint.
- New sheets must be of 0.50mm thick, JSW or TATA make.
- Total 10 no.s tranparent polycarbonate sheets must be provided in the roof.
- Height of the roof is approximately 15m.
- L- flash sheets of 500*500mm size must be provided in the junction of roof and vertical sheets of the adjacent building.
- All materials,labour, tools, consumables, safety PPEs etc., complete under the scope of contractor.

2. NBS monitor roof

- This work includes cutting& removal of damaged pieces of crimping sheets and purlins sets and refixing the newly fabricated purlins and sheets.
 - This work requires working above a roof at height of 43m.
 - Purlin in each span is 4 no.s (2 on each sides) and they are 3-point purlin fabricated from ISA 75*75*6 and solid round bar ISRO 20 as cross bracings.
 - Monitor roof is of 3m width, 1.5m on each side.
 - One coat of primer and two coats of enamel paint must be applied on the purlins.
 - ALL materials, labour, tools, consumables, safety PPEs etc., complete under the scope of contractor.
- ALL THE WORKS SHALL BE MEASURED FINALLY AS JOINT MEASUREMENT. FINAL BILLINGS WILL BE DONE ACCORDINGLY.





Udupi Cochin Shipyard Limited
Tender for Roof Repair Works at UCSL Malpe
UCSL/CC/T/CIVIL/242 Dt 11th March 2024

UCSL/CC/T/CIVIL/242 Dt 11TH MARCH 2024

TENDER FOR ROOF REPAIR WORKS AT UCSL MALPE

PRICE BID FORMAT

Sl. No.	Description	Quantity	Unit	Supply Amount (A)	Service Amount (B)
Part-A (NBS Monitor Roof Repair works)					
1	Replacement of 3-Point Purlins	5410	Kg		
2	Crimping Sheets	480	M2		
3	L-Flash Sheets (500 x 500 x 0.50mm thick)	300	Mtr		
Part-B (Pipe Shop roof sheet replacement works)					
4	Replacement of Roof Sheets & Purlin Painting as per scope of work	1342	M2		
5	Crimping Sheets	61	Mtr		
6	Total:				
7	Total (Part A+B) :				
8	CGST/SGST.....%				
9	Grand Total Amount:				
Grand total in words-					
i) The rates quoted should be all inclusive and shall include the service charges and other incidental expenditures, if applicable. ii) Quotes with Conditional rates / additional charges / Conditional discounts will be disqualified					

- L1 will be determined based on the serial no.07

Signature:

Date:

Address of the contractor:

Seal:

