



UDUPI COCHIN SHIPYARD LIMITED

(Formerly TEBMA Shipyards Limited)
Malpe Harbour Complex, Malpe,
Udupi, Karnataka – 576 108, India.
Tel – 0820 2538604.

TENDER FOR RENOVATION OF PIPE STORAGE SHED AT UCSL BAPUTHOTTA FACILITIES.

UCSL/CC/T/CIVIL/250 Dt: 20th APRIL 2024

Enquiry No. & date	UCSL/CC/T/CIVIL/250 Dt. 20 th APRIL 2024
Name of work	RENOVATION OF PIPE STORAGE SHED AT UCSL BAPUTHOTTA FACILITIES
Last date & time of receipt of tender	29 th April 2024 (Monday), 16:00hrs
Date & time of opening of Bid	29 th April 2024 (Monday), 16:00hrs

1. DESCRIPTION OF WORK

- 1.1. This enquiry pertains to the awarding of contract for Replacement of roof and vertical sheets of existing structure for pipe storage at UCSL Baputhotta facilities.
- 1.2. The work is to be carried out at Udupi Cochin Shipyard Limited (UCSL) facility, Udupi.

2. SCOPE OF WORKS

- 2.1. Roof Sheets are 0.47mm thick galvalume corrugated sheet, make JSW coloron+ or equivalent in TATA. (Procurement under the scope of the contractor)
- 2.2. Vertical sheets must be fixed with old good quality corrugated sheet present in UCSL premise.
- 2.3. Entire shed structural member including columns must be covered with one coat of primer and two coats of enamel painting. Members buffing must be done prior to painting.
- 2.4. Concrete pedestal must be covered with additional M20 grade concrete by 100mm on all 4 sides.
- 2.5. All the materials like Sheets, Self-tapping Screws, Primers, paints and all other consumables will be purchased by the contractor. The scope includes loading, unloading, shifting, stacking of such materials involved in the scope.
- 2.6. Contractor shall inspect the work site location before starting the work.
- 2.7. Mobilization of entire Labour/workmanship (skilled/semiskilled/unskilled) required for the work in accordance with the specification's provided by UCSL (After placement of work order) and applicable procedure shall be followed.





Udupi Cochin Shipyard Ltd
Tender for Renovation of Pipe Storage Shed at UCSL Baputhotta Facilities
 UCSL/CC/T/CIVIL/250 Dt 20th April 2024

3. SCOPE OF UCSL

- 3.1. Supply of old corrugated galvalume sheets. Contractor has to inspect the good condition sheets out of available materials. If any cropping of sheets is required it will be under the contractor's scope.
- 3.2. Electricity at the nearest location to the site will be provided. Contractor has to arrange proper cables for taking electricity at site.
- 3.3. Water for drinking and other purpose will be provided.

4. ADDITIONAL WORKS

- 4.1. This is a turnkey job and any additional works up to 5% growth of work on the Renovation of Pipe shed at UCSL- Baputhotta Facilities, in terms of addition of minor works to be envisaged and is to be undertaken without any additional price impact.
- 4.2. Any minor modifications, resulting from the change in statutory regulations prevailing at the time of final inspection of work by the statutory authority, to be carried out by the Contractor free of cost. In case of rework/modification/additional work, written consent is to be obtained from the UCSL officer-in-charge before commencement of the work.
- 4.3. Contractor shall execute, during or after completion of the work, any minor job connected with the work, that is considered necessary by Shipyard and/or statutory authority.
- 4.4. The contractor shall be responsible for any damage caused to the material supplied by UCSL. Compensation with penalty for damage or loss of the item will be recovered from the Contractor, in the event of loss or damage.

5. INDICATIVE QUANTUM OF WORK

SL No.	Particulars	Qty	UOM
1	Replacement of roof sheets with new 0.47mm thick galvalume sheets including materials, Labour, buffing & Painting of roof members, tools, consumables and scaffolding etc. complete	198	Sqm
2	Replacement of vertical sheets of the existing structure with old corrugated galvalume sheets including buffing & Painting of purlins tools, consumable, labour and scaffolding etc. complete.	223	Sqm
3	Providing and laying M20 grade concrete around the pedestals to increase their dimensions including shuttering, materials, labour, curing etc. complete.	1	Set

6. SCHEDULE OF COMPLETION

- 6.1. The work is urgent in nature hence, contractor to mobilize the men and material for execution of the work not later than 7 days from the placement of work order / Confirmation.

6.2. Work must be completed within 30 days from the date of Work Order.

