



UDUPI COCHIN SHIPYARD LIMITED

UDUPI COCHIN SHIPYARD LIMITED

Ministry of Ports, Shipping and Waterways,
Government of India

CONTRACT CELL DEPARTMENT

CORRIGENDUM - II

Tender No.: UCSSL/CC/T/CIVIL/285

Date: 29-08-2024

Sir,

CORRIGENDUM-II- TENDER FOR CONSTRUCTION OF FIRE PUMP ROOM & TOILETS

1. The following terms of the subject tender is amended as follows:

i. SCHEDULE OF COMPLETION

<u>FOR:</u>	<u>READ AS:</u>
Sl. No:6. SCHEDULE OF COMPLETION 6.2. Fire Pump work must be completed within 75 days from the date of Work Order	6.2. Fire Pump work must be completed within 60 days from the date of Work Order

2. Preferred make of items to be used for the scope of works.

- Plumb Fitting:** Cera, Hindware, Parryware, Jal, Ashirvad, Finolex or Astral.
- Electrical Fittings:** RR, Anchor, Havells or Legrand.

3. Price Bid format revised attached as Annexure-I

4. Bid Submission date extended up to 02nd September 2024 at 16:00hrs.

5. All the other terms and conditions of the tender enquiry remains unchanged.



For Udupi Cochin Shipyard Limited,

Assistant General Manager (Materials & Contract Cell)

सोणि क्लेमेन्ट टी एम
SONY CLEMENT T M
सहायक महाप्रबंधक/ASSISTANT GENERAL MANAGER
उदुपि कोचीन शिपयार्ड लिमिटेड
UDUPI COCHIN SHIPYARD LIMITED
माल्पे, कर्नाटक/MALPE, KARNATAKA-576 108



UDUPI COCHIN SHIPYARD LTD
TENDER FOR CONSTRUCTION OF FIRE PUMP ROOM & TOILETS
 UCSSL/CC/T/CIVIL/285 Dt 21ST AUG 2024

PRICE BID

Sl. No.	Description	Unit	Quantity (A)	Rate (B)	Total Amount (C=A x B)
I	Construction Fire Pump Room				
1	Earthwork in excavation & backfilling	M3	21.100		
2	Construction of 400mm thick foundation	M3	0.900		
3	Providing & Laying PCC bed in M15	M3	0.870		
4	150mm thick solid block masonry in CM 1:6	M2	36.500		
5	15mm thick internal plastering in CM 1:4	M2	70.750		
6	20mm thick external cement plastering in CM 1:4	M2	61.310		
7	Emulsion painting for both internal & external	M2	132.060		
8	Installation of rolling shutter	M2	3.800		
9	Providing & Laying RCC in M20 with shutter	M3	13.840		
10	Providing & Fixing FE-550 TMT bars	KG	1087		
			TOTAL (A):		
II	Construction of Workmen Toilet				
1	Construction of 400mm thick foundation	M3	3.950		
2	Providing & Laying PCC bed in M15	M3	2.100		
3	150mm thick solid block masonry in CM 1:6	M2	48.200		
4	15mm thick internal plastering in CM 1:4	M2	59.790		
5	20mm thick External cement plastering in CM 1:4	M2	43.050		
6	Emulsion painting for both internal & external	M2	67.290		
7	Fixing vitrified tile for wall & floor	M2	43.300		
8	Plumbing, door & windows, electrification works	SET	1		
9	Earthwork in excavation & backfilling	M3	6.700		
10	Supply and erection of structural roof	M2	20.147		
				TOTAL (B):	
III				Total (A+B):	
IV				GST @.....%	
V				Grand Total	
	Grand Total in words:				

* L1 will be determined based on the Sl No: V.

Name:
 Seal & Signature:
 Date:

