



UDUPI COCHIN SHIPYARD LIMITED

# UDUPI COCHIN SHIPYARD LIMITED

Ministry of Ports, Shipping and Waterways,  
Government of India

## CONTRACT CELL DEPARTMENT

### CORRIGENDUM - II

Tender No.: UCSSL/CC/T/CIVIL/298

Date: 15-11-2024

Sir,

### CORRIGENDUM-II – TENDER FOR CONSTRUCTION OF STRUCTURAL FOUNDATION FOR FIXING OF RAILS

1. The following terms of the subject tender is amended as follows:

FOR	READ AS
4.1. Dismantling R.C.C. concrete flooring including breaking concrete by chiseling, wedging etc. including cutting the reinforcement, stacking the serviceable materials and the debris separately upto a distance of 50 meter and shifting all the debris outside UCSSL premises, excluding the reinforcements etc., complete.	4.1. Dismantling R.C.C. concrete flooring including breaking concrete by chiseling, wedging etc. including cutting the reinforcement, stacking the serviceable materials and the debris separately upto 2Km (Approx) distance from UCSSL-Malpe to UCSSL-Kalmady plot or as directed by the engineer in charge.
4.2. Earthwork excavation in all soils including hard soils but excluding soft rock and hard rock, for foundations of walls, steps, footings, rafts, plinth beams, Cess pits, and in trenches including filling back. Excavation upto 1m depth, and stacking/shifting the soil upto 500m or as directed by the engineer in charge.	4.2. Earthwork excavation in all soils including hard soils but excluding soft rock and hard rock, for foundations of walls, steps, footings, rafts, plinth beams, Cess pits, and in trenches including filling back. Excavation upto 1m depth, and stacking/shifting the soil upto 2Km (Approx) distance from UCSSL-Malpe to UCSSL-Kalmady plot or as directed by the engineer in charge.
4.13. Collection, Transportation/unloading of base plates supplied by UCSSL from UCSSL Hangarakkattu facility to the work site at Malpe facility.	4.13. Collection, Transportation/unloading of base plates supplied by UCSSL from UCSSL Hangarakkattu facility to the work site at Malpe facility, will be done by UCSSL itself,
9.1. Movable shed foundation construction is required to be handed over within 60 days duration from the date of issue of the Work Order.	9.1. Movable shed foundation construction is required to be handed over within 60 days duration from the date of issue of the Work Order, with a grace period of additional 10 days, thus the total completion of entire scope of works will be maximum and limited to 70 days period only.





UDUPI COCHIN SHIPYARD LIMITED

# UDUPI COCHIN SHIPYARD LIMITED

Ministry of Ports, Shipping and Waterways,  
Government of India

## 2. Revised Payment Terms.

12.1. Payment will be done in Three (03) stages:

**STAGE-I:** 30% of the total contract value.

**Deliverables:** 80% of supply of TMT reinforcement bars against the supply of reinforcement steel as per the BOQ, 100% RCC Floor Chipping Works and 100% Earthwork in excavation for foundation.

**STAGE-II:** 40% of the total contract value.

**Deliverables:** On successful completion of all the RCC casting works.

**STAGE-III:** Final 30% of the total contract value.

**Deliverables:** On final handing over of the project with necessary test certificates.

3. Contractor should supply the TMT bar as per BBS (Bar Bending Schedule) and drawings, payment will be done on actuals/JMR (Joint Measurement Report).

4. All the other terms and conditions of the tender enquiry remains unchanged.

For Udupi Cochin Shipyard Limited,

Assistant General Manager (Materials & Contract Cell)

सोणि क्लेमेन्ट टी एम  
SONY CLEMENT T M  
सहायक महापबंधक/ASSISTANT GENERAL MANAGER  
उडुपि कोचीन शिपयार्ड लिमिटेड  
UDUPI COCHIN SHIPYARD LIMITED  
माल्पे, कर्नाटक/MALPE, KARNATAKA-576 108

