



UDUPI COCHIN SHIPYARD LIMITED

# UDUPI COCHIN SHIPYARD LIMITED

Ministry of Ports, Shipping and Waterways,  
Government of India

## CONTRACT CELL DEPARTMENT

### CORRIGENDUM - I

Tender No.: UCSSL/CC/T/CIVIL/310

Date: 25-01-2025

Sir/Madam,

### CORRIGENDUM-I -REMOVABLE SHED FABRICATION & ERECTION WORK

1. Change in scope

**For:**

**Structural tubular Frames:**

Steel work in built up tubular sections YST 310 grades as per IS: 4923 including cutting, hoisting, erecting in position, aligning the erected structures in line and level, bolting or welding wherever required as per drawing. complete with Hot finished seamless type tubes including painting applying two coats of aliphatic acrylic PU paint over two coats of epoxy cured with aliphatic amine over two coats of epoxy phenylalkamine primer, etc. closing all the open ends properly with same material, cost and conveyance of all materials, all accessories, hire charge of tools and plants, welding equipment, cost of electrodes, cost of bolts, nuts and washers all labour, other incidentals, etc. complete. (Provision of bolt holes to be made as required at no extra cost). All as per the drawings, technical specification and as directed by Engineer.

**Read As:**

**Structural tubular Frames:**

Steel work in built up tubular sections YST 310 grades as per IS: 4923 including cutting, hoisting, erecting in position, aligning the erected structures in line and level, bolting or welding wherever required as per drawing. Including painting applying two coats of aliphatic acrylic PU paint over two coats of epoxy cured with aliphatic amine over two coats of epoxy phenylalkamine primer, etc. closing all the open ends properly with same material, cost and conveyance of all materials, all accessories, hire charge of tools and plants, welding equipment, cost of electrodes, cost of bolts, nuts and washers all labour, other incidentals, etc. complete. (Provision of bolt holes to be made as required at no extra cost). All as per the drawings, technical specification and as directed by Engineer.

2. Revised Price bid format enclosed as Annexure- IV/A.
3. All the other terms and conditions of the tender enquiry remains unchanged.



For Udupi Cochin Shipyard Limited,

Assistant General Manager (Materials & Contract Cell)

सोणि क्लेमेन्ट टी एम  
SONY CLEMENT T M  
सहायक महाप्रबंधक/ASSISTANT GENERAL MANAGER  
उडुपि कोचीन शिपयार्ड लिमिटेड  
UDUPI COCHIN SHIPYARD LIMITED  
माल्पे, कर्नाटक/MALPE, KARNATAKA-576 108

**UDUPI COCHIN SHIPYARD LIMITED**Tender for Removable Shed Fabrication & Erection Work  
UCSL/CC/T/CIVIL/310**UCSL/CC/T/CIVIL/310****PRICE BID FORMAT**

Sl No.	Description	UOM	QTY	Rate	Total Amount
<b>Structural tubular Frames:</b>					
Steel work in built up tubular sections YST 310 grades as per IS: 4923 including cutting, hoisting, erecting in position, aligning the erected structures in line and level, bolting or welding wherever required as per drawing. including painting, applying two coats of aliphatic acrylic PU paint over two coats of epoxy cured with aliphatic amine over two coats of epoxy phenylalkamine primer, etc. closing all the open ends properly with same material, cost and conveyance of all materials, all accessories, hire charge of tools and plants, welding equipment, cost of electrodes, cost of bolts, nuts and washers all labour, other incidentals, etc. complete. (Provision of bolt holes to be made as required at no extra cost). All as per the drawings, technical specification and as directed by Engineer.					
<b>MAIN TRUSS</b>					
1	Rectangular Hollow section 122 x 61 x 3.6	Kg	901.51		
2	Square Hollow section 50 x 50 x 2.6	Kg	230.45		
3	Plate 16	Kg	72.42		
<b>TIE TRUSS</b>					
4	Rectangular Hollow section 122 x 61 x 3.6	Kg	380.45		
5	Square Hollow section 50 x 50 x 2.6	Kg	108.53		
<b>COLUMN</b>					
6	Pipe NB 150 x 7.1 Thick	Kg	1448.35		
7	Pipe NB 200 x 10.30 Thick	Kg	318.6		
8	Plate 16	Kg	82.06		
<b>PURLIN</b>					
9	Rectangular Hollow section 96 x 48 x 3.2	Kg	872.3		




**UDUPI COCHIN SHIPYARD LIMITED**

 Tender for Removable Shed Fabrication & Erection Work  
 UCSSL/CC/T/CIVIL/310

Sl No.	Description	UOM	QTY	Rate	Total Amount
	<b>SHEET</b>				
10	Providing and fixing precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12meter or as desired by Engineer In- charge. The sheet shall be fixed using self-drilling /self-tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. The colour of the sheet shall be in accordance with the approval of the Engineering In-charge.	Sqm	160		
11	Providing and fixing precoated galvanized steel sheet Gutter (200mm over all girth) 0.50 mm (+ 0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self-drilling/self-tapping screws.	Mtr	15		
12	<b>Total Basic Amount:</b>				
13	<b>GST/IGST.....%:</b>				
14	<b>Grand Total Amount:</b>				

\* L1 will be determined based on the Sl No: 14.

\* The rates quoted should be all inclusive and shall include the service charges and other incidental expenditures, if applicable.

\* **The above quantity is for one shed only; the total number of sheds is Three (03).**

Signature:

Date:

Address of the contractor:

Seal:

