



UDUPI COCHIN SHIPYARD LIMITED

UDUPI COCHIN SHIPYARD LIMITED

Ministry of Ports, Shipping and Waterways,
Government of India

CONTRACT CELL DEPARTMENT

CORRIGENDUM - I

Tender No.: UCSL/CC/T/CIVIL/309

Date: 07-01-2025

Sir,

CORRIGENDUM-I – TENDER FOR MOVABLE SHED FABRICATION & ERECTION WORK

1. The following terms of the subject tender (Annexure-I, Clause No: 2.14) is amended as follows:

SL. NO.	DESCRIPTION OF WORK	UOM	QUANTITY
1	Earth work in excavation up to 1.50-meter depth by mechanical means (Hydraulic excavator)/manual means in all kinds of soil including dressing of sides and ramming of bottoms, including cost and conveyance of all equipment, labour, dewatering and other incidental etc. and including disposal outside UCSL premises, all complete as directed by Engineer-In-Charge.	cum	280
2	Supplying, stacking and laying of hard granite soling stone 150 mm nominal size including packing with smaller stones wedging them tightly so that the whole is formed as sold mass, supplying and spreading 25 mm thick M sand and sweeping the same to fill the voids, watering properly and consolidating with roller including all labour, hire charges of roller, other incidental etc as per the direction of Engineer-in-charge	cum	68
3	Providing and laying plain cement concrete 1:4:8 using 40mm downgraded broken stones including cost and conveyance of all material, labour for mixing, laying, consolidating, curing etc complete and as per the direction of Engineer-in-Charge	cum	68




UDUPI COCHIN SHIPYARD LIMITED

 Tender for Skid Foundation Work at UCSL Hangarkatta
 UCSL/CC/T/CIVIL/309 DT: 02nd JANUARY 2025

SL. NO.	DESCRIPTION OF WORK	UOM	QUANTITY
4	Providing and casting Reinforced cement concrete 1:1.5:3 with 20mm downgraded coarse aggregate in required slope and position including cost of shuttering, de-shuttering, compacting with mechanical vibrators, hacking, curing, scaffolding, all equipment, labour, pumping, incidental expenses but excluding cost of reinforcement, complete as directed by Engineer in-charge.	cum	90
5	Supplying, cleaning, cutting, bending, supporting, binding with double ply of 22 SWG soft annealed wire and placing in position high yield strength deformed TMT reinforcement bars conforming to IS:1786 of grade Fe 500D or more of approved make on/at all levels and locations as per drawings, including handling and transport complete for all RCC works including supplying and & placing concrete cover block, all equipment, labour, incidental expenses complete as directed by Engineer in-charge	MT	8
6	Supplying and fabricating structural steel work conforming to IS 226/2062 including erecting in position, aligning the erected structures in line and level, welding holdfast wherever required as per approved drawing, cost and conveyance of all materials, labour, accessories, hire charge of tools and plants, welding equipment, cost of electrodes and applying two coat of synthetic enamel paint over a priming coat of Zinc chromate primer on the exposed surfaces/face of the structural member etc complete as directed by the Engineer-In-Charge	MT	18

- Revised Price bid format enclosed as Annexure- IV/A.
- All the other terms and conditions of the tender enquiry remains unchanged.

For Udupi Cochin Shipyard Limited,



Assistant General Manager (Materials & Contract Cell)

सोणि क्लेमेन्ट टी एम
 SONY CLEMENT T M
 सहायक महाप्रबंधक/ASSISTANT GENERAL MANAGER
 उडुपि कोचीन शिपयार्ड लिमिटेड
 UDUPI COCHIN SHIPYARD LIMITED
 माल्पे, कर्नाटक/MALPE, KARNATAKA-576 108



UDUPI COCHIN SHIPYARD LIMITED
Tender for Skid Foundation at UCSL Hangarkatta
UCSL/CC/T/CIVIL/309 DT: 2nd JANUARY 2025

UCSL/CC/T/CIVIL/309 DT: 02ND JANUARY 2025

TENDER FOR SKID FABRICATION AT UCSL HANGARKATTA SITE

REVISED PRICE BID FORMAT

Sl. No.	Description	Unit	Qty	Basic Rate	Basic Amount
1	Earth work in excavation up to 1.50-meter depth by mechanical means (Hydraulic excavator)/manual means in all kinds of soil including dressing of sides and ramming of bottoms, including cost and conveyance of all equipment, labour, dewatering and other incidental etc. and including disposal outside UCSL premises, all complete as directed by Engineer-In-Charge.	Cum	280		
2	Supplying, stacking and laying of hard granite soling stone 150 mm nominal size including packing with smaller stones wedging them tightly so that the whole is formed as solid mass, supplying and spreading 25 mm thick M sand and sweeping the same to fill the voids, watering properly and consolidating with roller including all labour, hire charges of roller, other incidental etc. as per the direction of Engineer-in-charge	Cum	68		
3	Providing and laying plain cement concrete 1:4:8 using 40mm downgraded broken stones including cost and conveyance of all material, labour for mixing, laying, consolidating, curing etc. complete and as per the direction of Engineer-in-Charge.	Cum	68		
4	Providing and casting Reinforced cement concrete 1:1.5:3 with 20mm downgraded coarse aggregate in required slope and position including cost of shuttering, de-shuttering, compacting with mechanical vibrators, hacking, curing, scaffolding, all equipment, labour, pumping, incidental expenses but excluding cost of reinforcement, complete as directed by Engineer in-charge.	Cum	90		
5	Supplying, cleaning, cutting, bending, supporting, binding with double ply of 22 SWG soft annealed wire and placing in position high yield strength deformed TMT reinforcement bars conforming to IS:1786 of grade Fe 500D or more of approved make on/at all levels and locations as per drawings, including handling and transport complete for all RCC works including supplying and & placing concrete cover block, all equipment, labour, incidental expenses complete as directed by Engineer in-charge	MT	8		



**UDUPI COCHIN SHIPYARD LIMITED**

Tender for Skid Foundation at UCSL Hangarkatta
UCSL/CC/T/CIVIL/309 DT: 2nd JANUARY 2025

Sl. No.	Description	Unit	Qty	Basic Rate	Basic Amount
6	Supplying and fabricating structural steel work conforming to IS 226/2062 including erecting in position, aligning the erected structures in line and level, welding holdfast wherever required as per approved drawing, cost and conveyance of all materials, labour, accessories, hire charge of tools and plants, welding equipment, cost of electrodes and applying two coat of synthetic enamel paint over a priming coat of Zinc chromate primer on the exposed surfaces/face of the structural member etc. complete as directed by the Engineer-In-Charge	MT	18		
7	Total:				
8	CGST/SGST.....%				
9	Grand Total Amount:				

Grand total in words-

i). The rates quoted should be all inclusive and shall include the service charges and other incidental expenditures, if applicable.

ii). Quotes with Conditional rates/additional charges/Conditional discounts will be disqualified.

- L1 will be determined based on the serial no.09

Signature:

Date:

Address of the contractor:

Seal:

