



UDUPI COCHIN SHIPYARD LIMITED

Ministry of Ports, Shipping and Waterways,
Government of India

CONTRACT CELL DEPARTMENT

CORRIGENDUM - I

Tender No.: UCSL/CC/SER/T/CSL/262/2026

Date: 31-07-2026

Sir,

**CORRIGENDUM-I - TENDER FOR STRUCTURAL STEEL STRENGTHENING WORKS FOR
INSTALLATION OF TWO (02) NOS. 25 TON ELECTRIC OVERHEAD TRAVELLING (EOT)
CRANES AT ALUMINIUM FABRICATION SHOP, COCHIN SHIPYARD LIMITED.**

The following terms of the subject tender are amended as follows

1. Pre-bid meeting date; **04th August 2026 (Tuesday)**
2. Tender Opening Date;

FOR	READ AS
05 th August 2026 (Wednesday), 15:30HRS	07 th August 2026 (Friday), 15:30HRS

3. The 16 mm plates required for main girder strengthening and the 6 mm plates required for column strengthening will be supplied by UCSL. Bidders shall consider these plates as being under the scope of supply of UCSL.
4. The Quantity also amended in the scope of work. enclosed as Revised Price bid Format. annexure-III-A.
5. All the other terms and conditions of the tender enquiry remains unchanged.

For Udupi Cochin Shipyard Limited,

अखिल आर पी
AKHIL R P
प्रबंधक MANAGER
उदुपि कोचीन शिपयार्ड लिमिटेड
UDUPI COCHIN SHIPYARD LIMITED
माल्पे, कर्नाटक/MALPE, KARNATAKA-576 108

Assistant General Manager (Contract Cell)



Udupi Cochin Shipyard Limited

TENDER FOR INSTALLATION OF EOT CRANES AT ALUMINUM FABRICATION BAY AT CSL FOR

UCSL

UCSL/CC/SER/T/CSL/262/2026 Dt 23rd July 2026

UCSL/CC/SER/T/CSL/262/2026 Dt 23rd July 2026
REVISED PRICE BID FORMAT

Sl.No	Description	Unit	Quantity	Rate	Total Amount
1	Removing the existing crane rail from top of the girder, provided at a height of 13 m above ground level, by unbolting the M16 bolts spaced at 384 mm c/c and releasing the clamps and fish plate, using suitable crane and stacking the rail, bolts and clamp at a location within 50m from site as directed by the Engineer-in-charge within CSL premises, to be reused once again excluding bolts. Rate quoted shall include all works such as providing scaffolding, unbolting and removal of bolt and clamp and fish plate and bringing down the clamps, bolts, fish plates and rail and transporting and stacking them at specified location including cost of all men, material, machinery and equipments including providing safety harness etc. all complete.	Tonne	20		
2	Cleaning and carrying out surface preparation of the area in the girder/columns for receiving the additional flange plate in beams and web plate in column using suitable equipments and tools as described in the technical specification including cost of providing scaffolding, men, material, machinery and equipment including providing safety harness etc. all complete.	m2	290		





Udupi Cochin Shipyard Limited

**TENDER FOR INSTALLATION OF EOT CRANES AT ALUMINUM FABRICATION BAY AT CSL FOR
UCSL**

UCSL/CC/SER/T/CSL/262/2026 Dt 23rd July 2026

3	fabricating and providing, additional flange plate at top and bottom of the existing girder, providing web plates to selected columns to augment the capacity of beam and column as per drawing and technical specifications and approved fabrication shop drawings, including providing necessary scaffolding and all necessary operations such as but not limited to preheating as per specifications, straightening, bending, cutting, punching, drilling required holes for bolting the clamps to fix rail, grinding, threading, machining if required, welding, erecting etc. complete including cleaning using wire brush, mechanical tools or by using suitable chemical methods, grinding and removing the welding burr, scales and applying one coat of approved Zinc Chromate primer as per the technical specifications and as directed by Engineer- in- Charge including providing safety harness all complete. Gas Cutter shall not be permitted to drill the required hole in the flange plate. (Fabrication drawing is to be prepared by the contractor and got approved from the Engineer-in-Charge before commencement of work)	tonne	24.33		
4	Transporting the dismantled rail and clamps stacked at the storage place and re-erecting the same at location as shown in the drawing by providing and fixing M16 bolts of suitable length and providing necessary joints to rail using fish plates including cost of all men, materials, machinery, equipments and tools including providing necessary scaffolding including providing safety harness etc. all complete	m	290		
5	Painting over fabricated structural members Application of two coats of synthetic enamel paint over one coats of zinc chromate primer of approved quality and colour, conforming to technical specification, including cost of providing scaffolding, materials, labour, other incidentals including providing safety harness etc. all complete as instructed by Engineer-in- Charge.	m2	320		
6	TOTAL AMOUNT				
7	GST				
8	GRAND TOTAL AMOUNT				





Udupi Cochin Shipyard Limited
TENDER FOR INSTALLATION OF EOT CRANES AT ALUMINUM FABRICATION BAY AT CSL FOR
UCSL
UCSL/CC/SER/T/CSL/262/2026 Dt 23rd July 2026

****Note:**

- i. L1 will be arrived based on the lowest total amount quoted at Sl.No.06
- ii. In the case of error in multiplication/ addition in the amount calculated, the unit rate quoted will be calculated accordingly.
- iii. The above indicative list of items along with respective quantities (not limited) shall be considered as minimum requirement for preparing the quotation, if any additional item other than those specified above is required for the satisfactory completion of project as per the scope of work shall be under scope of contractor under no extra cost.
- iv. Payment shall be done based on the actual quantity of work executed.
- v. Quotes with Conditional rates / additional charges / Conditional discounts will be disqualified.

Signature:

Address of the contractor:

Seal:

